

# ORGANOCLAY Permeable Reactive Barrier Utilized to Control NAPL Contamination

The groundwater at a former creosote wood treating site was contaminated by non-aqueous phase liquid (NAPL). The contaminated groundwater was a threat to the nearby fresh water bay when NAPL and soluble organics were showing on the surface of the bay.



## PROJECT DETAILS

Bay Project – Union Pacific Railroad  
Engineer: Ch2M Hill  
Contractor: Ch2M Hill Construction  
Subcontractor: DeWind Dewatering

## LOCATION

Escanaba, MI

## PRODUCTS USED

BULK ORGANOCLAY®  
REACTIVE CORE MAT®

Approximately 15 ft (5 m) up gradient of the RCM a permeable reactive barrier wall was installed. One part organoclay was mixed with 3 parts of ¼ inch (6 mm) pea gravel by volume in a stockpile. A continuous trenching machine placed the organoclay-gravel mix in an 18 inch (45 cm) wide by 10 ft (3 m) deep by 240 ft (80 m) long trench. The organoclay PRB was completed in one day.

## CHALLENGE:

As part of the remediation strategy, the use of an permeable reactive barrier was included in the design utilizing bulk ORGANOCLAY® filled REACTIVE CORE MAT® (RCM).

## SOLUTION:

To stop the pollution from spreading through the bay and into Lake Michigan, an interim measure was taken which consisted of installing a permeable reactive barrier (PRB) containing ORGANOCLAY® media and CETCO REACTIVE CORE MAT® (RCM) along the affected stretch of beach and a permeable reactive wall behind the RCM.

# ORGANOCLAY Permeable Reactive Barrier Utilized to Control NAPL Contamination

**RESULT:**

The sheen dissipated from the fresh water bay as soon as the RCM and PRB was installed and brought online. The installed cost for mobilization/demobilization, RCM installation, PRB installation, site restoration, and waste disposal was approximately \$220,000. The organoclay RCM and PRB have worked successfully for three years. Piezometers were installed upstream and downstream of the PRB. The piezometers indicate that there is no mounding of the upstream groundwater. There is DNAPL present the central upstream piezometer, but no DNAPL in the respective downstream piezometer. Also, no sheen has been observed emanating from the RCM.

North America: 847.851.1800 | 800.527.9948 | [www.cetco.com](http://www.cetco.com)

UPDATED: SEPTEMBER 2017

© 2017 Minerals Technologies Inc. IMPORTANT: The information contained herein supersedes all previous printed versions, and is believed to be accurate and reliable. For the most up-to-date information, please visit [www.cetco.com](http://www.cetco.com). CETCO accepts no responsibility for the results obtained through application of this product. CETCO reserves the right to update information without notice.

